

P.O.Box 236, Tororo Gen:+256-454448842 Dir: +256-454448864 Mob: +256-782999874 Fax: +256-454436517

Email:ar@acadreg.busitema.ac.ug Website:www.busitema.ac.ug

FACULTY OF ENGINEERING DEPARTMENT OF WATER RESOURCES AND MINING ENGINEERING

WATER RESOURCES ENGINEERING PROGRAMME

FINAL YEAR PROJECT REPORT

DESIGN AND CONSTRUCTION OF A SEMI-AUTOMATED SOLAR POWERED MACHINE FOR REMOVING FLOATING WASTE IN DRAINAGE CHANNEL.

(CASE STUDY: NAKAMIRO DRAINAGE CHANNEL IN BWAISE)

BY

DRIBAREO FIONA

BU/UP/2017/1486

+256786560834/750411651

dribareofiona@gmail.com

PROJECT SUPERVISORS: MR. LUBAALE SOLOMON AZARIUS AND
MR. BAAGALA BRIAN SEMPLIJA

ABSTRACT

Due to the ever-increasing World population, there has been resultant increase in resource consumption which has been manifested by increased waste generation.

Waste management is a very crucial aspect of society organization, especially in urban areas. In the case of poor waste management, toxic waste is hazardous to living animals, aquatic life and plants. When solid waste is not managed well especially in line with disposal, it accumulates in drainage channels. Accumulation of solid waste in drainage channels is associated with very detrimental effects such as clogging/blockage of the drainage channels, flooding and breakout of waterborne diseases due to stagnancy of waste water.

A semi-automated solar powered machine for removing floating waste in drainage channel will be designed and constructed to counter accumulation of solid waste in the Nakamiro drainage channel in Bwaise. The prototype operates automatically by the use of sensors and has mainly the lifting mechanism which is powered by a D.C motor to run it, getting its power from either a solar charged battery having solar panel fixed on top or an electric rechargeable battery. The lifters also carry out delivery of the lifted waste to the collection bin built on the machine. The machine executes the function of extracting trapped solid waste from the drainage channel as they are shepherd to the machine and trapped by the screen on the machine, which will solve the problem of solid waste accumulation in the channel along with its resultant evils.

This machine will effectively minimize on the accumulation of solid waste in the flowing waste water in the channel. Upon significant reduction of solid waste in the channels, blockage will also be significantly reduced or/and completely avoided and its detrimental effects as well as minimizing treatment costs of the waste water downstream.

The machine was technically evaluated and it was found to have a work rate of 9.84kg/min and an overall operational efficiency of 94.64%. Having cost Shs.1,466, 000, economic evaluation of the project was done and it was found to be viable with a Net Present value of Shs.95,925,733 and profitability index of 65.

The improved drainage channel cleaning machine was successfully designed, fabricated and assembled. I recommend the compaction and use of at least two ultrasonic sensors to obtain right bin height and ensure maximum utilization of the bin volume.

DRIBAREO FIONA i BU/UP/2017/1486

DECLARATION

I **DRIBAREO FIONA**, do hereby declare to the best of my knowledge, that this final year project report is an outcome of my original work and that it has never been presented to any institution of learning for an academic award. All the work contained in this report is as a result of my research except where cited.

Signature	 	· • • •	 	• • •	 	 	 	 •
Date	 		 		 	 	 	

DRIBAREO FIONA ii BU/UP/2017/1486

with approval from the supervisors.				
Supervisors;				
Mr. LUBAALE SOLOMON AZARIUS	Mr. BAAGALA BRIAN SEMPIJJA			
Signature	Signature			
Date	Date			

This final year project report is submitted to the Faculty of Engineering for examination

APPROVAL

DEDICATION

This report is dedicated to my sponsor FAWEU Chapter and my beloved family, my dad Mr. Madra Richard, mom Mrs. Alia Beatrice, my brother Hedga, my sisters Keller, Tracy, Barbra, Mercy and friends in appreciation for their selfless care and unwavering support provided to me since childhood, and for the spirit of hard work, courage and determination instilled in me, which attributes I have cherished with firmness and have indeed made me what I am today.

ACKNOWLEDGEMENT

In such a vast undertaking of this nature, it is impossible to reach and acknowledge every contribution and sundry. However, the temptation to acknowledge the following is irresistible.

I would like to extend my long heart felt gratitude to God Almighty for knowledge and wisdom, strength, protection, love and above all the gift of life to do the little things that I was able to do. The glory and honor is to Him forever and ever.

I am particularly indebted to MR. LUBAALE SOLOMON AZARIUS for being such a wonderful supervisor under whose guidance I was able to come up with such a research final project.

I am also thankful to my family for being supportive during this period of my project research.

Special thanks go to Barasa Eddy, Wanjusi Lasto and Natkunda Loyce for lending me a helping hand as I undertake my project.

DRIBAREO FIONA v BU/UP/2017/1486

LIST OF FIGURES

Figure 1: Culverts are filled with garbage in (a) and (b). (c) shows KCCA employee removing
sediments filling a channel in Bwaise while (d) show a damaged secondary channel [9]
Figure 2: Flooding in the town due to the blockage of drainage channels [10]
Figure 3: Waste management at Kitezi landfill [21]
Figure 4: Typical solid waste management pattern in Uganda [23]
Figure 5: Hand tools used by workers to remove solid waste from channels
Figure 6: Casual laborers removing solid waste using hand tools [28]
Figure 7: An excavator [29]14
Figure 8: The trash-rack cleaning machine [30].
Figure 9: Drainage patterns in Bwaise parish III [31]
Figure 10: A flow chart showing the design, construction, assembly and automation of the
system
Figure 11:Block diagram of Ultrasonic Distance Detection with Arduino . Error! Bookmark no
defined.
Figure 12:The ultrasonic distance sensor module with working process [38] Error! Bookmark
not defined.
Figure 13:Arduino UNO Based on ATMega-328 Microcontroller [40] Error! Bookmark no
defined.

LIST OF TABLES

Table 1:The different components of the machine were fabricate	d as shown in the table; Error!
Bookmark not defined.	
Table 2: A number of considerations were made in material sele	ction for the different machine
components as shown in the table	.Error! Bookmark not defined.
Table 3:Assembly of the different components to construct the p	prototype was done as shown in
the table below;	.Error! Bookmark not defined.
Table 4: Layout for the tabulation of the test results.	.Error! Bookmark not defined.
Table 5: Table of Results from the moment and shear force com-	putations 33
Table 6: Table showing the weights of the different machine cor	nponents 38
Table 7: Results from the Machine Components design analysis.	40

Table of Contents

ABSTRACT	i
DECLARATION	ii
APPROVAL	iii
DEDICATION	iv
ACKNOWLEDGEMENT	v
LIST OF FIGURES	vi
LIST OF TABLES	vii
1.0 CHAPTER ONE: INTRODUCTION	1
1.1 Background	1
1.2 Statement of the problem	2
1.3 Research objectives	4
1.4 Justification of the study	4
1.5 Significance of the study	4
1.6 Scope of the project	5
1.7 CONCEPTUAL FRAMEWORK	6
2.0 CHAPTER TWO: LITERATURE REVIEW	7
2.1 Waste	7
2.2 Classification of solid waste.	7
2.3 Sources of waste	7
2.4 Waste management	8
2.4.1 Waste handling practices.	9
2.4.2 Poor waste management	10
2.4.3 Effects of poor waste management.	11
2.4.4 The current methods of Solid waste management in drainage channels	12
2.4.6 Challenges associated with the current methods of cleaning drainage channel	16
2. 5 Case study area – Nakamiro drainage channel in Bwaise III Parish	17
2.5.1 Map showing Location of Nakamiro drainage channel in Bwaise parish III	18
3.0.CHAPTER THREE: METHODOLOGY	19

3.1 Objective one: To design the different components of the machine	19
3.1.1 Redesign considerations	19
3.1.2 Machine description	20
3.1.4 Designing of the different components of the Drainage Cleaning Machine	22
Design of the control system	39
4.1.1 Summary of machine component specifications	40
4.2 To fabricate and assemble the different components to form a prototype	41
4.2.1 Fabrication of different components of the machine.	41
4.2.2 Assembly of the different components to construct the machine was done by the formethodology and sequence.	_
4.3 To test the performance of the machine	45
4.3.1 After the tests were done, the following, results were obtained	45
4.3.2 Analysis of the results.	46
4.4 To carry out economic analysis of the machine	46
CHAPTER FIVE. CONCLUSIONS, CHALLENGES AND RECOMMENDATIONS	51
5.1 Conclusions	51
5.2 Challenges.	51
5.3 Recommendations.	51
Appendices	53